CERTIFIED LAND CORNER RESTORATION

Index No. Q-11

State of Wisconsin
County of Oneida } ss.

I Philip T. Hansen, do hereby certify that on the 22nd day of May, 1978, I ~~found~~ established ~~xxxxxxxx~~ the SC 1/16 corner of Section 21 Township 35, North, Range 11 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Glen Barker

Jim Claflin

Herb Wagoner

WISCONSIN PHILIP T. HANSEN ARGONNE, WIS. S-498 LAND SURVEYOR



○ = Corner monument restored.

History of original corner establishment:

No record of any previous survey.

Description of corner evidence found:

No evidence of any corner recovered.
Established corner by traverse and computation. Ran the E-W and N-S 1/4 lines from previously established 1/4 corners to establish the center 1/4 corner. C 1/4 corner computed at 2562.691 feet, N 0° 01' 27" E of south 1/4 corner. Set SC 1/16 at 1231.346 feet intermediate. Corner fell in ditch line of Stockley - Meister Road.

Description of monument and accessories I established to perpetuate the original location of this corner.

Set a 1½" x 18" iron pipe for true corner in ditch line 6" below the surface.
Set a 1½" iron pipe with 2" brass cap, 22 ft. east for witness corner.
Monument projects 30" above ground. Cap stamped:
Marked NBT's to true corner -
White Pine 7" N59°E, 28.25 feet
Maple 7" N82°W, 87.05 feet, scribed 1/16 BT

S498
T35N R11E
SC 1/16 S 21 W.C.
W - 22 ft.
CPI-1978

Dated at Rhinelander, Wis., this 5th day of June, 1978.

Signature Philip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the 26th day of June, 1978 at 11:35 o'clock a M.

Doris Verage Kuehn
(Register of Deeds)

By ..... Deputy

FORM 985 H. G. MILLER CO., MILWAUKEE

35/11/21/10 20