CERTIFIED LAND CORNER RESTORATION

Index No. D-15

State of Wisconsin
County of Oneida } ss.

I Philip T. Hansen, do hereby certify that on the 21st day of September, 19 76, I found evidence of the C 1/16 corner of Section 3 Township 37, North, Range 9 east, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Hamlin

Herb Wagoner



O = Corner monument restored.

History of original corner establishment:

Corner established by W. Rollins and crew, Rhinelander Surveyors, in 1958.
Ran ranks N. line North from S 1/4 corner, bearing 355° 30' Mag., 79.[illegible] chains to close out 1.22 chains west of N 1/4 corner.
Set C 1/16 corner at 19.89-3/4 chains, 30-1/2 links east.
Marked BTs - Black Spruce 2½" S 16° W 19½ links.
Black Spruce 4" N 50° W 43 links.

Description of corner evidence found:

Recovered 3/4" iron pipe with 2 x 2" square brass cap stamped:
Monument projects 12" above ground.
Recovered Black Spruce 4" N 50° W 45.0 links, scribed C 1/16 on BT.
Black Spruce 3" S 16° W 19.85 links, scribed C 1/16 on BT. (now dead)



Description of monument and accessories I established to perpetuate the original location of this corner.
As the monument was recovered in good condition, it was left as found, but added T37N R9E stamping to brass cap.
Marked BT - Black Spruce 6" N 35° W 40.2 links, scribed 1/16 BT.
Monument and BTs painted blue.

Dated at Rhinelander, Wis., this 4th day of October, 1976

Signature Philip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida I hereby certify that the within instrument was filed in this office for record on the 9th day of November, 19 76 at 10:30 o'clock A M.

Doris Verage Kuehn
(Register of Deeds)

By ..... Deputy

FORM 985 H. C. MILLER CO., MILWAUKEE

37090310 20