

CERTIFIED LAND CORNER RESTORATION

Index No. **C-17**

State of Wisconsin

County of Oneida } ss.


I Phillip T. Hansen, do hereby certify that on the 19th day of July, 1977, I found evidence of the Quarter corner of Section 2 & 3 Township 37 North, Range 9 East, Fourth Principal Meridian,

as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Claflin

Herb Wagoner




History of original corner establishment: Original Corner established by Wm. E. Dougherty, Deputy Surveyor, in 1863, from which Birch 8" bears S40°W, 21 links and Birch 8" bears N17°E, 11 links. Corner re-established by N. Loftus, Ripco Surveyor, in 1955. Ran random line N4°W, 73.99 chains to Section Corner 34, 35, 2 & 3. Set 1/4 corner at 38.65 chains. Marked NBTs - White Pine 16" S44°W, 64.5 links. Tamarack 6" N54°E, 63.5 links.

Description of corner evidence found:

Recovered 1/2" re-enforcing rod and 1/4" iron pin in center of old Highway 17. Also 2" iron pipe with 4" square brass cap, 25 links west of pin in road. Recovered OBTs - White Pine 16" (20") S44°W, 64.5 links (65.2 links), scribing not legible. Tamarack 6" N54°E, 63.5 links, our bearing N58°E, dist. 64.4 links.

Description of monument and accessories I established to perpetuate the original location of this corner. As monument was recovered in excellent condition, it was left as recovered.

Cap is stamped: Monument projects 28" above ground. NBT - Black Spruce 7" S89°E, 59.5 links, scribed 1/4 RT. T37N R9E S3 - S2 1/4 Corner 25 lks. East RIPCO



○ = Corner monument restored.

Dated at Rhinelander, Wis., this 28th day of July, 1977

Signature: *Phillip T. Hansen* Title: Registered Land Surveyor Registration No. S-498 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida. I hereby certify that the within instrument was filed in this office for record on the 5th day of August, 1977 at 9:00 o'clock P.M.

Signature: *Louise Vergees Kuehn* (Register of Deeds)

By: Deputy

3709032000