

CERTIFIED LAND CORNER RESTORATION

Index No. V-13

State of Wisconsin

County of Oneida

ss.

I Philip T. Hansen

, do hereby

certify that on the 18th day

of February 19 77, I found

evidence of the Section

corner of Section 27, 28, 33, 34

Township 37 North, Range



9 East, Fourth Principal Meridian,

as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Claflin

Herb Wagoner



○ = Corner monument restored.

History of original corner establishment:

Original Corner established by Wm. E. Dougherty, Deputy Surveyor, in 1863, from which White Pine 15" bears S 81° E 8 links and White Pine 20" bears N 56° W 16 links.

Corner recovered by N. Loftus, Ripco Surveyor, in 1961. Ran random line North bearing N 12° 51' E from Quarter corner between Section 33 & 34, 41.87 chains, to close out 183 links East of corner. Marked Tamarack 10" S 70° E 74-3/4 links and Tamarack 7" S 11° E 70-1/2 links.

Description of corner evidence found:

Recovered 1 1/2" iron pipe with alloy cap in excellent condition. Also an old 1 1/2" iron pipe along side of it. Cap stamped:

Recovered OBTS - Tamarack 10" S 70° E 74.75 links (69.75 links).
Tamarack 7" S 11° E 70.5 links (74.5 links).

T37N R9E
28 | 27
33 | 34
RIPCO

Description of monument and accessories I established to perpetuate the original location of this corner.

As corner was recovered in excellent condition, it was left in place.

NBTs - Maple 7" S 34° W 54.0 links, scribed SC BT.
Maple 7" N 34° W 61.6 links, scribed SC BT.

Dated at Rhineland, Wis., this 21st day of March, 19 77

Signature Philip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Registrar of Deeds, County of Oneida. I hereby certify that the within instrument was filed in this office for record on the 18th day of February, 19 77 at 4:30 o'clock P.M.

Walter George Kuehn
(Registrar of Deeds)

By: _____ Deputy

3709280000