

CERTIFIED LAND CORNER RESTORATION

Index No. **K-19**

State of Wisconsin

County of Oneida } ss.

I Philip T. Hansen, do hereby certify that on the 28th day of October, 1975, I found evidence of the NC-1/16 corner of Section 14



Township 37, North, Range 11 East, Fourth Principal Meridian,

as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Glen Barker

Jim Claflin



○ = Corner monument restored.

History of original corner establishment: Original corner established by J.J. Melendy, Gagen Lumber Company surveyor. Set cedar post and marked BT's: Spruce 4" N150E 18 links and Spruce 4" N690W 11 links. Corner recovered by H.C. Lawrence, Registered Land Surveyor, in 1954. Recovered old post and BT's intact. Set new cedar post.

Description of corner evidence found: Recovered 5" cedar post, squared and scribed NC-1/16 Sec. 14, N-1/16 S14, in fair condition sitting beside Melendy's old post. Scribing not visible. Recovered OBT's: Spruce 4" N150E 18 links - now decayed stump, Spruce 4" N670W 11 links - now decayed stump. Measurements check to old stake recovered.

Description of monument and accessories I established to perpetuate the original location of this corner. Replaced Melendy's old cedar post with 1" OD iron pipe with 2" brass cap stamped -

Post projects 12" above ground. Lawrence's 5" cedar post remains standing beside new pipe. NBT's: Black spruce 4" N820E 64 links - scribed 1/16 BT, Black spruce 5" S120W 57.4 links - scribed 1/16 BT. T37N R11E S498 NC-1/16 S14 CPT-1975

Dated at Rhineland, Wis., this 7th day of November, 1975.

Signature *Philip T. Hansen* Title, Registered Land Surveyor Registration No. S-498 (County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida. I hereby certify that the within instrument was filed in this office for record on the 9th day of November, 1976 at 1:30 o'clock P.M.

Gene George Kuehn (Register of Deeds)

By Deputy