

CERTIFIED LAND CORNER RESTORATION

Index No. **X-23**

State of Wisconsin



County of Oneida } ss.

I Phillip T. Hansen, do hereby certify that on the 25th day of February, 1977, I found evidence of the C 1/4 corner of Section 36

Township 38, North, Range 7 East, Fourth Principal Meridian,

as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:  
Jim Craftin  
Herb Wagoner



History of original corner establishment:

Corner established by B.F. Dorr, County Surveyor, Corner recovered by Goddard and crew, Ripco Surveyors, in 1959. Ran random line East from West 1/4 corner. Recovered Dorr's C 1/4 corner at 39.82 chains. Set new iron pipe and marked NBTs - Tamarack 8" S 79° E 15 1/2 links, Tamarack 8" S 49° W 9 1/2 links, and Tamarack 8" S 40° E 26 1/2 links.

Description of corner evidence found:

Recovered 1 1/2" iron pipe with 3" brass cap, stamped: Monument projects 24" above ground.  
Recovered 1 1/2" iron pipe with 3" brass cap, stamped: Monument recovered in good condition.  
Recovered OBTs - Tamarack 8" S 49° W 9.5 lks. (9.0 lks.), scribed C 1/4 S 36 BT.  
Tamarack 8" S 40° E 26.5 lks., scribed C 1/4 S 36 BT.  
No evidence of Tamarack BT S 79° E. sec. 36 R1Pco

Description of monument and accessories I established to perpetuate the original location of this corner.

As monument was recovered in good condition, it was left in place.  
Added stamping T38N R7E to cap.  
NBT - Black Spruce 7" N25°E 50.1 links, scribed 1/4 BT.

Dated at Rhineland, Wis., this 23rd day of March, 1977.

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida  
Instrument was filed in this office for record on the 1st day of April, 1977 at 10:30 o'clock A.M. I hereby certify that the within

Phillip T. Hansen  
(Register of Deeds)

By Phillip T. Hansen Deputy

3807362020