CERTIFIED LAND CORNER RESTORATION

Index No. V-16

State of Wisconsin }
County of Oneida } ss.

I Philip T. Hanson, do hereby certify that on the 20th day of October, 19 77, I found evidence of the E 1/16 corner of Section 27 & 34 Township 38, North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Claflin

[illegible]

WISCONSIN PHILIP T. [illegible] S-4[illegible]6 LAND SURVEYOR



○ = Corner monument restored.

History of original corner establishment:

Corner established by N. Loftus, Pipco Surveyor, in 1959. Ran random line 91° 10' bearing 121.75 chains from Section Corner 27, 28, 33 & 34 to close out 2.67 chains south of 1/4 corner between Sections 26 & 35, a good corner, corrected bearing N 89° 57' E. Set E 1/16 corner by proportion at 59.90-3/4 chains, 1.314 chains north of random. Marked BTs - Aspen 6" N45°E, 47' links
Aspen 9" N34°[illegible], 22 links

Description of corner evidence found:

Recovered 3/4" iron pipe with 2" square brass cap in good condition.
Recovered BTs - Aspen 9" (13") N34°[illegible], 22.0 links, scribing grown over.
Aspen 6" N45°[illegible], 47.5 links, [illegible] blazed [illegible].

Description of monument and accessories I established to perpetuate the original location of this corner.

As monument was recovered in good condition, it was left in place.
[illegible] Cap stamped:
Marked BTs - Maple 4" N70°[illegible], 44.2 links
Maple 4" N40°[illegible], 27.6 links
Both BT scribed 1/16 BT.

E 1/16 $\frac{28 | 27}{33 | 34}$ PIPCO

Dated at Rhinelander, Wis., this 2nd day of November, 19 77

Signature *Philip T. Hanson* Title Registered Land Surveyor Registration No. S-[illegible]
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the 12th day of December, 1977 at 11[00] o'clock a M.

Doris Verage Kuehn
(Register of Deeds)

By *Joseph M. Boomer* Deputy

381027[00]10

FORM 985 H. C. MILLER CO., MILWAUKEE