Index No. U-12

CERTIFIED LAND CORNER RESTORATION

State of Wisconsin } ss.
County of Oneida

I Philip T. Hansen, do hereby certify that on the 25th day of October, 1977, I found evidence of the SE 1/16 corner of Section 28 Township 38, North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Claflin

Mark [illegible]

WISCONSIN PHILIP T. HANSEN [illegible] WIS. S-498 LAND SURVEYOR



○ = Corner monument restored.

History of original corner establishment:

Corner established by W. Loftus, Fire Surveyor, in 1939. From recovered S 1/16 corner established by Vaughan, ran random line bearing [illegible] 11' W., 20.065 chains to close at 11 links north of S 1/16 on east line. Corrected bearing S 85° 50' E. Set SE 1/16 corner at 19.991 chains intermediate.
Marked BTs - Red Maple 6" S32°E, 81 links
Hemlock 8" N26°W, 29 links.

Description of corner evidence found:

Recovered 3/4" iron pipe with 2" square brass cap in good condition.
Monument projects 20" above ground. Cap stamped:
Recovered BTs - Red Maple 6" (9") S32°E (S38°E) 8.5 links (9.0 lks)
[illegible] 8" (9") N26°[illegible] (N21°[illegible]) 29.6 links (29.0 [illegible]).
[illegible] SE 1/16 [illegible]

SE 1/16 [illegible] [illegible]

Description of monument and accessories I established to perpetuate the original location of this corner.

No additional accessories established.

Dated at Rhinelander, Wis., this 7th day of November, 1977

Signature *Philip T. Hansen* Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the *12th* day of *December*, 19*77* at *11:00* o'clock *a* M.

Doris Verage Kuehn
(Register of Deeds)

By *Joseph M. Boomer* Deputy

FORM 985 H. C. MILLER CO., MILWAUKEE

38/028/010