

CERTIFIED LAND CORNER RESTORATION

Index No. **7-4**

State of Wisconsin

County of Oneida



ss.

I Phillip T. Hansen, do hereby certify that on the 20th day of February, 1978, I found evidence of the EC 1/16 corner of Section 30 Township 38 North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Clafflin

Herb Wagoner



○ = Corner monument restored.

CERTIFIED LAND CORNER RESTORATION

History of original corner establishment:

Corner established by N. Loftus, Ripco Surveyor, in 1956. Ran random line west N 86° 37' W from re-established E 1/4 corner 82.00 chains to close out 1.59 chains south of W 1/4 corner. Established C 1/4 corner at 40.77 chains. Set EC 1/16 corner at 20.384 chains intermediate. Corrected bearing N 85° 31' W.

Marked NBT's - cedar 4" S72°W, 28 links  
cedar 4" S11°E, 20 links

Description of corner evidence found:

Recovered 3/4" iron pipe with a 2" square brass cap in good condition.  
Recovered 4" cedar (6") S72°W (S78°W) 28 links, scribbling grown over  
4" cedar (5") S11°E, 20.0 links  
Monument projects 24" above ground. Cap stamped:

E 1/16  
C ——— C  
S30  
RIPCO

Description of monument and accessories I established to perpetuate the original location of this corner.  
Monument left in place as recovered.

No additional accessories established.

Dated at Rhinelander, Wis., this 6th day of March, 1978

Signature Phillip T. Hansen Title Registered Land Surveyor Registration No. S-498  
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida  
Instrument was filed in this office for record on the 13th day of March, 1978  
at 2:30 o'clock P. M.

Doree Verage Kuehn  
(Register of Deeds)

By \_\_\_\_\_ Deputy