CERTIFIED LAND CORNER RESTORATION

Index No. W-7

State of Wisconsin } ss.
County of Oneida

I Philip T. Hansen, do hereby certify that on the 28th day of February, 1978, I found evidence of the NC 1/16 corner of Section 32 Township 38, North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Jim Claflin

Herb Wagoner



O = Corner monument restored.

History of original corner establishment:

Corner established by N. Loftus, Ripco Surveyor, in 1957.
From previously established C 1/4 distance between N 1/4 corner and C 1/4 was 39.81 chains.
Set NC 1/16 corner at 19.90½ chains on bearing N 2° 30' W. Found Dorr's 8" pine burned hard, no iron marks visible. Set iron pipe and marked NBT's - tamarack 7" S48°W, 57½ links; red maple 5" N37°E, 62 links.

Description of corner evidence found:

Recovered 1" iron pipe with 2" square brass cap in good condition, projecting 20" above ground. Cap stamped:
Recovered OBT's - tamarack 7" S48°W, 57.5 links, no trace evident.
red maple 5" (8") N37°E, 62 links, scribing grown over.

C
N 1/16 | S32
C
RIPCO

Description of monument and accessories I established to perpetuate the original location of this corner.

Monument left in place as recovered.
Marked NBT - Maple 6" N83°E, 37.7 links, scribed 1/16 BT.

Dated at Rhinelander, Wis., this 6th day of March, 1978.

Signature Philip T. Hansen Title Registered Land Surveyor Registration No. S-498
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the 13th day of March, 1978 at 2:30 o'clock P. M.

Doris Verage Kuehn
(Register of Deeds)

By ..... Deputy

38/032/30/22

FORM 985 H. C. MILLER CO., MILWAUKEE