CERTIFIED LAND CORNER RESTORATION

Index No. Y-13

State of Wisconsin
County of Oneida } ss.

I Philip T. Hansen, do hereby certify that on the 21st day of October, 1977, I found evidence of the S 1/16 corner of Section 33 - 34 Township 38, North, Range 10 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Resident witnesses:

Wm. Claflin [illegible]

Herb Wagener [illegible]

WISCONSIN
PHILIP T. HANSEN
S-623
LAND SURVEYOR
[illegible]

T38N R10E



○ = Corner monument restored.

History of original corner establishment:

Corner established by N. Loftus, [illegible] Surveyor, in 1856. Ran random line north from section corner 33, 34, 3 & 4, bearing N 1° 22' W a distance of 113.[illegible] chains to close out [illegible] links west of 1/4 corner between Section 27 & 28.
Set S 1/16 corner at [illegible] 10.72 chains [illegible] links east.
Corner sets in an open bog. No trees available for BTs.

Description of corner evidence found:

[illegible] 1 3/4" iron pipe with 2" brass cap in good condition.
No evidence of any BTs visible. Cap stamped:

S 1/16 S33 | S34

Description of monument and accessories I established to perpetuate the original location of this corner.

Monument [illegible] left in place [illegible] recovered.
Monument projects 12" above ground.
Established 2 [illegible] monuments.
1 - 1" iron [illegible], projects 2[illegible]" above ground.
2 - 3/4" iron [illegible], 50 links, projects 24" above ground.
Corner [illegible] of small pond.

Dated at Rhinelander, Wis., this 2nd day of November, 1977

Signature *Philip T. Hansen* Title Registered Land Surveyor Registration No. S-[illegible]
(County Surveyor, Registered Land Surveyor, or other duly authorized official)

Office of Register of Deeds, County of Oneida, I hereby certify that the within instrument was filed in this office for record on the 12th day of December 1977 at 11:00 o'clock A. M.

Doris Verage Kuehn
(Register of Deeds)

By *Joseph M. Boomer* Deputy

FORM 985 H. C. MILLER CO., MILWAUKEE

3810331000