

6	5	4	3	2	1
7	8	9	10	11	12
13	14	15	16	17	18
19	20	21	22	23	24
25	26	27	28	29	30
31	32	33	34	35	36

T 39 N, R 03 E

RECEIVED & FILED
 Price County Surveyor's Office
 Date 2009.09.24
 By RES
 PCS File No. N3820
E0300
2008

CERTIFIED LAND CORNER RESTORATION

REGISTER OF DEEDS OFFICE
 ONEIDA COUNTY
 FILED



STATE OF WISCONSIN
 COUNTY OF Price

MAR - 9 2016

I, Randy R. Ericksn, do hereby certify that on the 15 day of Sept., 2008.

I found evidence of the Southeast corner of Section 24, Township 39 North, Range 03 East, Fourth Principal Meridian, as described hereon; and that from this evidence I established a new monument and accessories as described hereon to perpetuate the original location of this corner.

Description of Original monument and accessories and subsequent restorations:

1864 Alex Anderson set a wood post and marked Bearing Trees:
 Cedar 7" N 42° W 17 links Cedar 8" N 53° E 16 links
 Birch 7" S 80° E 3 links White Pine 14" S 65° W 13 links

1936 U.S. General Land Office dependent resurvey located original corner position based on found original Bearing Trees. Set an iron post, 3 ft. long, 2" dia., 27" in ground with brass cap stamped to identify the corner. Remains of original BTs: White Pine Stump 24" S 65° W 13 links, Rotted Cedar Stump N 42° W 17 links. Marked new Bearing Trees:

Cedar 5" N 78° E 27 links Cedar 8" S 08 1/4° E 44 links
 Cedar 5" S 77° W 22 links White Birch 6" N 13° W 54 links

Description of corner evidence found:

Found 1936 iron post monument in place. Found 1936 Cedar BT S 08 1/4 E 44 lks alive, now 12" dia. Found 24" stump of Cedar BT N 78° E 27 links.

Found Wisconsin Conservation Department Aluminum tag on a Cedar 17" N 88° E 24.27 feet. Found a Nekoosa Paper Co. Aluminum Tag on a Maple 13" S 30° W 22.68 feet.

Description of monument and accessories I established to perpetuate the location of this corner:

Left 1936 iron post monument in place. Current Bearing Trees:
 Cedar 12" S 08° E 29.0 feet (U.S. GLO 1936)
 Cedar 17" N 88° E 24.27 feet (Wisconsin Department of Conservation)
 Maple 13" S 30° W 22.68 feet (Nekoosa Paper Company)
 Steel sign post North 0.9 feet

Established Wisconsin North Zone State Plane Coordinates for Corner:

N 247893.032 E 1957388.331 NAD 83 1991 U.S foot

Section	24
Town	39 North
Range	03 East

● - Corner monument restored

Resident witnesses _____
 Dated at Park Falls Wisconsin, this 29 day of Sept 2008
 Signature [Signature] Title Reg. Land Surveyor
 Surveyors Registration No. 1897
 Office of _____ County of _____
 I hereby certify that the within instrument was filed in this office for record on the _____ day of _____ 20_____, and was filed in Book No. _____ Page No. _____ of County Records.
 Signature _____ Title _____

Township 39 North, Range 03 East, Section 24, Index No. _____, Page No. _____

From Price City Surveyor 390324 0000

N3820 E0300 2008

R-1